

## **Bids for Golf Villa 100 Front Walkway**

Golf Villa 100 front walkway surface coating is delaminating and popping up causing not only an unsightly appearance but also a serious safety issue.

Need to do this work now before traffic picks up. These funds would come from the building reserves.

We recommend the bid from Northwest Florida Coatings. They are already on property doing other work and can start this as soon as materials can be obtained.

Thanks

Bayside paint Contracting LLC

10441 Miller Circle  
Youngstown, FL 32404

# Estimate

Date	Estimate #
10/3/2019	Villas 100

Name / Address
Richard Clark Edgewater

Project

Description	Qty	Rate	Total
Mechanically remove coating from second floor walkway to expose concrete.		0.00	0.00
Apply Vulkum primer to exposed concrete.		0.00	0.00
Apply caulk to perimeter of walkway		0.00	0.00
Apply Vulkum 350/351 at 1 coat and broadcast anti skid medium.		0.00	0.00
Apply a 2cd coat of Vulkum 350/351 to seal the anti skid medium.		0.00	0.00
Included in cost: Clean up of generated debris from job, material, and equipment.		35,950.00	35,950.00
<b>Total</b>			<b>\$35,950.00</b>

Phone #
(850) 774-6853

E-mail
baysidepaintcontracting@gmail.com

NW Remodeling LLC

PO Box 1920  
Panama City Beach, FL  
32407

# Estimate

Date	Estimate #
1/7/2020	1

Name / Address
Richard Clark Edgewater

			Project
Description	Qty	Rate	Total
Mechanically remove coating from second floor walkway to expose concrete.		0.00	0.00
Apply Vulkum primer to exposed concrete.		0.00	0.00
Apply caulk to perimeter of walkway.		0.00	0.00
Apply Vulkum 350/351 at 1 coat and broadcast anti skid medium.		0.00	0.00
Apply 2cd coat of Vulkum 350-351 to seal the anti skid medium.		0.00	0.00
Included in cost: Clean up of generated debris from job, material, and equipment.		36,950.00	36,950.00
		<b>Total</b>	<b>\$36,950.00</b>

Northwest Florida Coatings LLC  
 8103 Panama City Beach parkway  
 Panama City Beach, FL 32407  
 US  
 8502768283  
 robertscuba75@gmail.com

# Estimate

ADDRESS  
 Richard Clark  
 Edgewater

SHIP TO  
 Richard Clark  
 Edgewater  
 Edgewater

ESTIMATE #            DATE  
 1152                    10/02/2019

P.O. NUMBER  
 Villa 100

DATE	ACTIVITY	DESCRIPTION	QTY	RATE	AMOUNT
10/02/2019		Grind all coating off of second floor walkways to bare concrete			
10/02/2019		Prime bare floor with Vulkem Primer			
10/02/2019		Caulk perimeter of walk way floor			
10/02/2019		Apply 1 Coat of Vulkem 350/351 pedestrian traffic coating and broadcast non skid aggregate			
10/02/2019		Apply 2nd coat of Vulkem top coat to lock down non skid			
10/02/2019		Re-coat all steps leading up to walkways and repair stucco columns NO CHARGE	0		0.00
10/02/2019	<b>Sales</b>	Price includes all labor, materials , equipment and clean up			28,500.00
<b>TOTAL</b>					<b>\$28,500.00</b>

Accepted By

Accepted Date

Signed \_\_\_\_\_ Date \_\_\_\_\_

Signed \_\_\_\_\_ Date \_\_\_\_\_